



**BASES CONVERSION and DEVELOPMENT AUTHORITY**

2/F Bonifacio Technology Center, 31st Street Bonifacio Global City, Taguig City

Tel. No. 8575-1700 loc. 1782/1784

Email: [vmnatividad@bcda.gov.ph](mailto:vmnatividad@bcda.gov.ph)

**REQUEST FOR QUOTATION**

(Company Name):

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Date: **31 March 2026**

PR #: **0002177**

Please quote your lowest price(s) using this form, or your letterhead. Also, take note of the following details:

- 1) Quotation/s shall be addressed to the Head of Procurement Division. Please indicate Solicitation or Reference No.
- 2) Send the said quotation/s to BCDA or fax the same at no. 8575-1785 not later than 4/8/2026, 5:00 pm
- 3) Quotation/s submitted after the set deadline indicated in item no. 2 shall not be accepted/considered.
- 4) The quotation/proposal shall be properly signed by the authorized representative and/or immediate supervisor.

*BCDA reserves the right to accept or reject any or all of the quotations, or waive formally therein, or to accept quotation/s as may be considered most advantageous to the gov't., or to pursue appropriate legal action should the winning bidder refuse to accept the award without justifiable reason/s.*

**VICKY NATIVIDAD**  
Cavasser

**ALMIRA S. CLARIANES**  
Chief Administrative Officer

TO: BCDA HEAD OF PROCUREMENT						
Per request, below is/are the price(s) of the article(s)/service(s) as indicated under Unit Price:						
QTY (A)	UNIT	DESCRIPTION/SPECIFICATIONS	UNIT COST (ex-VAT) (B)	VAT (C)	TOTAL UNIT COST (D = B + C)	TOTAL AMOUNT (A x D)
1	Lot	<b>PROCUREMENT OF STICKERS FOR ROAD SIGNAGES AND REAPPLICATION OF THERMOPLASTIC PAVEMENT MARKINGS FOR ROADS at NEW CLARK CITY</b>				
		ABC Php 2,000,000.00				
		<b>For the Scope of Works, Deliverables and Qualifications of this Procurement</b> ( please refer on the attached Terms of Reference (TOR) and Technical Specifications <b>For the Scope of Works, Quantiy and Site Photos</b> (Annex "A") <b>Warranty Security</b> : Please refer to the TOR				
		<b>Delivery Locations:</b> New Clark City, Capas, Tarlac				
					<b>TOTAL AMOUNT</b>	₱

Documentary Requirements upon submission of quotation:

- 1) Valid Mayor's/Business Permit
- 2) PhilGEPS Registration No.
- 3) BIR Certificate of Registration (BIR Form 2303)
- 4) Income/Business Tax Return if the ABC is above 500k
- 5) Omnibus Sworn Statement and Proof of Authorization

(Upon notification of Notice of Award-winning bidder must submit within 5 working days the duly NOTARIZED OSS and Proof of Authorization e.g., Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)

**Terms and conditions:**

- Price: **Inclusive of all applicable taxes**
- Payment: **NET Thirty (30) working days**
- Delivery: \_\_\_\_\_ day/s (upon conforme of P.O.)
- Validity of price: **one (1) month**
- WARRANTY: at least one (1) year**

We hereby certify, that we have prepared, checked and reviewed this quotation. This quotation is valid unless revoked in writing which should be done prior to our receipt of the Purchase Order or Job Order.

**SCOPE OF WORK, DELIVERABLES AND QUALIFICATIONS  
(Bidders must put Comply/Non Comply on the Column provided)**

The Contractor shall provide all labor, materials, equipment, tools, supervision, and other resources necessary for the removal, replacement, and installation of road thermoplastic markings, road signage stickers, and other related works within New Clark City.

The scope of work shall include, but not be limited to, the following:

<b>Description</b>	<b>Comply /Non Comply</b>
<p>1. <u>Removal of Existing Thermoplastic Road Markings</u></p> <ul style="list-style-type: none"> <li>● Removal of the remaining and deteriorated thermoplastic road and parking markings along Road 1, Road 2, Athletics Stadium, and Aquatics Center of New Clark City.</li> <li>● Proper surface preparation prior to the application of new thermoplastic markings.</li> </ul>	
<p>2. <u>Reapplication of Thermoplastic Road Markings</u></p> <ul style="list-style-type: none"> <li>● Supply and installation of new thermoplastic pavement markings in accordance with applicable road safety standards.</li> <li>● Application of road markings along Road 1 and Road 2, which serve as the primary road network of New Clark City.</li> </ul>	
<p>3. <u>Aquatics Center Pavement Markings</u></p> <ul style="list-style-type: none"> <li>● Installation and reapplication of thermoplastic pavement markings at the Aquatics Center parking areas and driveways to ensure proper traffic flow and safety.</li> </ul>	

<ul style="list-style-type: none"> <li>• Application of other markings and repainting of other items listed in <b>Annex A</b>.</li> </ul>	
<p>4. <u>Athletic Stadium Pavement Markings</u></p> <ul style="list-style-type: none"> <li>• Installation and reapplication of thermoplastic pavement markings at the Athletics Stadium driveways to ensure proper traffic flow and safety.</li> </ul>	
<p>5. <u>Replacement of Road Signage Stickers</u></p> <ul style="list-style-type: none"> <li>• Removal of faded, damaged, or peeling road signage stickers.</li> <li>• Supply and installation of new reflectorized road signage stickers to ensure high visibility during both daytime and nighttime conditions.</li> </ul>	
<p>6. <u>Repainting of Concrete Parking Blocks and Aquatics Center Curbs</u></p> <ul style="list-style-type: none"> <li>• Surface preparation and repainting of existing concrete parking blocks and driveway curbs located at the Aquatics Center parking area.</li> </ul>	
<p>7. <u>Parking Line Markings at the Athletes Village</u></p> <ul style="list-style-type: none"> <li>• Painting of parking slot lines within the Athletes Village parking areas.</li> </ul>	
<p>8. <u>PWD Parking Markings</u></p> <ul style="list-style-type: none"> <li>• Painting and installation of Persons With Disabilities (PWD) parking markings and symbols within the Athletes Village in accordance with accessibility standards</li> </ul>	
<p>9. <u>Traffic Management and Safety</u></p> <ul style="list-style-type: none"> <li>• Provision of temporary traffic control measures, safety signages, and personnel during the execution of works to ensure the safety of road users and workers</li> </ul>	



***The Contractor shall deliver the following outputs:***

<b>Description</b>	<b>Comply /Non Comply</b>
a. Completed Removal and Replacement of Thermoplastic Road Markings along Road 1, Road 2, Aquatics Center parking areas, and other identified locations	
b. Installation of Reflectorized Road Signage Stickers replacing faded and damaged signage stickers.	
c. Repainted Concrete Parking Blocks at the Aquatics Center using black and yellow rubberized paint.	
d. Completed Parking Line Markings within the Athletes Village parking areas.	
e. PWD Parking Markings properly installed and compliant with accessibility guidelines.	
f. Thermoplastic Pavement Markings applied at the Aquatics Center parking areas and driveways.	
g. Completion Report documenting the works undertaken, including photos and documentation of completed installations and markings.	

***Interested contractors meet the following minimum qualifications***

<ul style="list-style-type: none"> <li>• Must be a duly registered company with the appropriate government agencies (SEC, DTI, or CDA).</li> </ul>	<i>To be attached to the Quotation</i>
<ul style="list-style-type: none"> <li>• Must possess a valid PhilGEPS registration.</li> </ul>	<i>To be attached to the Quotation</i>
<ul style="list-style-type: none"> <li>• Must comply with Occupational Safety and Health (OSH) standards and implement necessary safety measures during project execution.</li> </ul>	
<p><b><u>Submission of Single Largest Contract (SLCC) at least 50% of the ABC related to the project to be bid during submission of bid</u></b></p> <ul style="list-style-type: none"> <li>• Must have prior experience in road marking works, thermoplastic pavement markings, traffic signage installation, or similar infrastructure works.</li> <li>• Must have access to appropriate thermoplastic road marking equipment and tools.</li> <li>• Must employ qualified personnel with experience in road safety marking installation and traffic control.</li> </ul>	

## **TECHNICAL SPECIFICATION**

All works shall comply with DPWH road safety standards and specifications for road markings and traffic signages.

The thermoplastic pavement markings to be applied under this project shall comply with the following minimum technical specifications:

<b>Description</b>	<b>Comply /Non Comply</b>
1. <u>Material Type</u>  i. Hot-applied thermoplastic road marking material suitable for concrete pavement surfaces	

2. <u>Thickness</u>	
i. Minimum 2.5 mm thickness after application.	
3. <u>Color</u>	
i. White and yellow thermoplastic materials shall be used depending on the type of road marking.	
4. <u>Surface Preparation</u>	
i. Pavement surfaces must be clean, dry, and free from dust, oil, grease, or loose materials prior to application.	
5. <u>Application Temperature</u>	
i. Thermoplastic materials must be heated and applied in accordance with the manufacturer's recommended temperature and application guidelines.	
6. <u>Durability</u>	
i. Materials shall be designed for high-traffic road conditions and resistant to weather exposure and abrasion.	
7. <u>Compliance</u>	
i. All materials and installation shall comply with DPWH Standard Specifications for Highways, Bridges and Airports (Blue Book)	

**I. DELIVERY PERIOD**

The duration of the project shall be Sixty (60) Calendar Days from the date of issuance of Notice to proceed.

**II. LOCATION**

National Government Administrative Center (NGAC), New Clark City, Brgy. Aranguren, Capas, Tarlac, specifically the Athlete's Village.

**III. APPROVED BUDGET FOR THE CONTRACT**

**Two Million Pesos & 0/100 Centavos only (Php 2,000,000.00)** inclusive of VAT and all applicable government taxes and fees, chargeable to the BCDA General Appropriations Act (GAA).




**ANNEX A**  
**SCOPE OF WORK, QUANTITY AND SITE PHOTOS**






PROCUREMENT OF STICKERS FOR ROAD SIGNAGES AND REAPPLICATION OF  
THERMOPLASTIC PAVEMENT MARKINGS FOR ROADS








**SCOPE OF WORK AND QUANTITY**







The Contractor shall provide all labor, materials, equipment, tools, supervision, and other resources necessary for the removal, replacement, and installation of road thermoplastic markings, road signage stickers, and other painting works listed.

The corresponding quantities for each item of work are presented in the table below.




<b>Reflectorized Thermoplastic Pavement Markings</b>						
<b>Item</b>	<b>Color</b>	<b>Width (m)</b>	<b>Total Length (m)</b>	<b>Actual Photo</b>	<b>Comply/ Non Comply</b>	
ROAD 1 AND ROAD 2 (Four Lane Road)	Centerline	White	0.20	1340 m		
	Broken Line	White	0.15	2,765 m		
	Edge Line	White	0.10	2,765 m		
	<b>Others</b>	<b>Color</b>	<b>Quantity</b>	<b>Unit</b>	<b>Actual Photo</b>	





	Road Arrows 1	White	22	pcs		
	Road Arrows 2	White	2	pcs		
	Pedestrian Lines	White	6 (21.243 sqm. each set)	set		
	Yellow Box	Yellow	1 (w=20 cm)	unit		
	PWD Ramp	White	12	sets		
Aquatics Center	Arrow 1	White	20	pcs		




	Arrow 2	White	4	pcs		
	Arrow 3	White	1	pcs		
	Arrow 4	White	2	pcs		
	Car Parking Lines	White	23	pcs		
	Bus parking lines	White	10	pcs		
	Yellow square (parking)	Yellow	26	pcs		
	Parking Stripes	Black and White	1	set		

	Lines	White	18 (1m x 0.15m each)	pcs		
	Roundabout	White and Yellow	1 (dia=6.07 m)	set		
Athletics Stadium	Arrow 1	White	9	pcs		
	Arrow 2	White	2	pcs		
	Arrow 3	White	2	pcs		
	Pedestrian Lines	White	3 (9 sqm. each set)	sets		

<b>Reflectorized Thermoplastic Stickers for Road Signages</b>				
<b>Type of</b>	<b>Quantity</b>	<b>Dimension</b>	<b>Actual Picture</b>	<b>Comply/Non</b>

Signage				Comply
Bicycle Lane	24 pcs	Dia = 60 cm		
Slow Down Ped Xing Ahead	2 pcs	42 cm x 67.5 cm		
Pedestrian Crossing	17 pcs	Dia = 60 cm		

Curve Ahead	2 pcs	H=55 cm, W=60cm		
Intersection Ahead	4 pcs	H=55 cm, W=60cm		
Stop	4 pcs	Length of one side = 25 cm		
Cul-De-Sac	1 pc	44 cm x 60 cm		

<b>OTHER PAINTING WORKS</b>				
<b>Type</b>	<b>Color</b>	<b>Quantity</b>	<b>Location/Photo</b>	<b>Comply/Non Comply</b>
Parking Lines	Reflectorized Paint (White)	51.5 sq.m. (103m x 0.1m)	Athletes Village 	
Pedestrian Parking road sign	Thermoplastic Marking (White)	4 set	Athletes Village 	
Concrete Parking Barrier	Reflectorized Black and Yellow	26 pcs (2m x 0.225 m)	Aquatics Center 	
Curb	Reflectorized Black and Yellow	Approximately 400m length	Aquatics Center	

				
--	--	--	--	--